

The fuel and utilities are transferred from the storage facility and services via underground piping, beneath the access pad and gangway, and thence to the Fuel Dock. The overall observed condition of the Dock is that there are minor levels of deterioration being observed. However, in January 2018 a contracted engineer (EMC – Engineers/Scientists, LLC) inspected the concrete landing system that provides access to the Fuel Dock.

Management had concerns because they had noticed an increase in gap had been developing between the concrete pad landing and the approaching concrete stairway to the landing. The consulting engineer made the following conclusions and recommendations: “the pad, underlying supports soils and riprap are failing along a slip surface estimated to be a sector of about 26 feet from the theoretical center of moment, which provides a surface resisting force of about 30 feet in length. It is noted that the lowest elevation of the slip is several feet higher than the designated H beam support. The existing slip of the system westward will continue. When the failure occurs the attached lines and conduit are likely to be severed. Additionally the gangway approach to the fuel Dock from the pad would be damaged possibly lost.”¹⁹

To remedy this the fuel lines must be rerouted, concrete landing removed, loosened underlying soils and riprap removed and the approaching slopes stabilized, tieback/deadman system, correctly designed, or specified H-beam pile, with penetration designed to be driven to several feet below the theoretical slip surface. Adequate subgrade, bedding and leveling course placed, topped with reinforced concrete landing (at least 4” thick). Safety rails and security should then be installed. It has been noted by Port Management that the replacement of the concrete access landing may only provide a somewhat temporary solution. As is the case with the afore-described shipping/receiving docks, the stability of the soils has been compromised from high and recharged upper groundwater flows.

Consequently the soils have lost friction value (loss of soil cohesion), resulting in the development of slip surfaces underground.

An alternative and preferred remedy to H-beam and/or tie back is to convert the floating dock to a fixed dock. Doing so removes the ever-present threat of slope failure and damage to gangway and utility/fuel lines. A sheet pile wall with tie-back would be constructed, and then filled with engineered material to level. Precast concrete pads would be placed atop the compacted fill and leveling course. Fuel and utilities would then be connected without concerns from failing slopes, tide surges or severed/damaged utility/fuel lines.

Views of this commercial Dock are provided in Exhibit A, Page 7. The location of this Dock on Port grounds could be seen in Figures 1.3 and 1.4 of this Grant Project narrative.

Transient and Work Docks

These two docks are service docks, utilized for shipping and receiving alongside moorage, maintenance activities, and loading/unloading.

¹⁹ See Exhibit E-5, Page 3, Conclusion.

The docks themselves are in fair condition, but are held in place by shallow driven, creosote-coated piles²⁰. As discussed previously, creosote is no longer an acceptable preservative with respect to the well-being of marine life. Additionally, the piles themselves are in poor condition. Given the very high costs for the mobilization of barge and crane equipment necessary to remove shipping/receiving dock pile, timber and concrete pad systems as proposed in this narrative, it would be helpful to utilize said equipment to place properly installed and specified, Coded coated steel piles in place of these creosote – coded coated piles. Views of this commercial Dock are proved in Exhibit A, Page 8. The location of this Dock on Port grounds could be seen in Figures 1.3 and 1.4 of this Grant Project narrative.

Access, Parking and Material Handling Surfaces

Access, parking and material handling to the Docks (Phase I Resurfacing, about 215,000 ft.²) identified in this narrative is very poor and it inefficient. These surfaces are strewn with potholes, filled with water during rainy season, comprised of compacted gravels, severely degraded asphalt and soil surfaces²¹. Material handling is estimated to be about 80% of the total cost for operations at these docks (forklift unloading of product, placement of product, retrieval and storage of crab pots, nets, gear, etc.). Observations made by Port management, and interviews with yard operators have indicated that the normal retrieval of crab pots, for example, including the retrieval of crab pots, the movement of totes, and the unloading of commercial vessels take about seven minutes per trip on these very poor surfaces.

If the services were properly paved (asphalt is recommended) those trips would be reduced from seven minutes to about a minute and a half, constituting a savings of 4.7 minutes per trip. With the estimated 3500 trips per week, 7 to 8 months per year (typically from December to August) a sizable annual savings of over 8,000 man-hours and 4000 machine hours would be received by the Shipping/Receiving Dock operations, and an approximately equal savings by the delivering commercial vessels. Additionally, legal and protective stormwater/industrial wastewater management would be implemented in the Phase III surfacing areas as a result of this subproject.

Another benefit, aside from the vastly increased efficiency of fishing operations that would be gained by the resurfacing of these areas, would be the control and reduction of the recharge to upper groundwater that is occurring during rainfall. The mounded groundwater serves to accelerate erosion of the Ports embankments beneath the Shipping/Receiving Dock structures.

Additionally, the maintenance, servicing, storage and launching of vessels via the Travel Lift Dock are performed in the adjacent boat yard (Boat Yard Resurfacing, about 2.7 acres). At present all of these surfaces are of gravel or soils. Paving these services would provide eased Travel Lift routing from the Dock to the storage and work areas, and would increase much-needed boat storage and service area. As would be the case for the Phase I resurfacing subproject, legal and protective stormwater/industrial wastewater management would be implemented in the Boat Yard as a result of this project.

²⁰ (Footnote – Exhibit A, Transient Dock - Support Structure, Photos 1 - 4; Work Dock – Support Structure, Photos 1 & 2).

²¹ See Exhibit C, Photo #s 1 – 9.

FUEL DOCK REPLACEMENT SCHEDULE

Engineer's Estimate - 2/24/19

Month	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	
Year	19																21									22

1	Final Project Design																										
2	Permitting Period																										
3	Contractor Procurement Award, Workplan																										
4	Completion, Order Mtls. Erosion & Pollution																										
5	Control																										
6	Mobilization																										
7	Removal of Structures, Obstructions																										
8	Relocate Existing Outbuildings Lighting																										
9	General Excavation																										
10	Furnish and Drive Steel Sheet Piling																										
11	Structure Excavation																										
12	Construct Deadman																										
13	Nonwoven Filter Geotextile																										
14	Place General Backfill																										
15	Stone Embankment																										
16	Furnish and Install Steel Tieback Rods																										
17	Complete Backfill																										
18	Complete Concrete Pad & walkway areas																										
19	Reinstall Illumination																										
20	Furnish & Install Dockside Hoist																										
21	Fuel Line Update & Replacement																										
22	Demolish Old Fuel Dock																										
23	Final Inspection																										

Note: Contractor must continue in-water work (sheet pile driving) for the rest of the docks in Phase I. At 3 - 4 piles driven per day, Pac-Choice (175 piles, 50 days) and Old BC Fisheries (180 piles, 52 days), The total in-

PHASE I RESURFACING

Engineer's Estimate - 2/16/19

Month	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	
Year	19																21								22
1 Design & Project Engineering																									
2 Permitting																									
3 Erosion Control																									
4 Mobilization																									
5 Project Layout/Mtls. Testing																									
6 Site Preparation/Demolition																									
7 Excavation & Grading																									
8 Geotextile Fabric																									
9 Aggregate Sub-Base																									
10 Cleanouts & Catch Basins																									
12 Utility Boxes																									
13 Waterline Installation																									
14 3" Asphalt Overlay (215,000 sf) (150 lbs/cf)																									
15 Conveyance Pipe																									
16 Trench Drain																									
17 CIP Curb																									
18 Curb & Gutter																									
19 Concrete Sidewalk																									
20 Electric Conduit & Wiring																									
21 Lighting w Foundation																									
22 Landscaping & Plantings																									
23 Striping																									
24 Final Inspection																									

This six-month period is best for completing the proposed Phase I paving project, for at least 3 reasons:

1. The dry season begins in April at this location, providing amenable conditions for asphalt & concrete work;
2. This six-month time period is outside the in-water work period (Oct. - end of February), and so the surfacing work need not conflict with proposed in-water (dock repair/replacement) and
3. All resurfacing work should be done after that requiring heavy equipment (cranes, excavators) has been done at the Fuel, Pac-Choice and Old BC Fisheries Shipping/Receiving Docks, in order to prevent damage to new (asphalt) surfaces.

00

HALLMARK ROAD & YARD RESURFACING Engineer's Estimate - 2/17/19

Month	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10
Year	20											21										22

1	Design & Project Engineering																					
2	Permitting																					
3	Erosion Control																					
4	Mobilization																					
5	Project Layout/Mtls. Testing																					
6	Site Preparation/Demolition																					
7	Excavation & Grading																					
8	Geotextile Fabric																					
9	Aggregate Sub-Base																					
10	Cleanouts & Catch Basins																					
12	Utility Boxes																					
13	Waterline Installation																					
14	3" Asphalt Overlay (215,000 sf) (150 lbs/cf)																					
15	Conveyance Pipe																					
16	Trench Drain																					
17	CIP Curb																					
18	Curb & Gutter																					
19	Concrete Sidewalk																					
20	Electric Conduit & Wiring																					
21	Lighting w Foundation																					
22	Landscaping & Plantings																					
23	Striping																					
24	Final Inspection																					

This six-month period is best for completing the proposed Phase III paving project, for at least 3 reasons:
 1. The dry season begins in April at this location, providing amenable conditions for asphalt & concrete work;
 2. This six-month time period is outside the in-water work period (Oct. - end of February), and so the surfacing work need not conflict with proposed in-water (dock repair/replacement) and
 3. All resurfacing work should be done after that requiring heavy equipment (cranes, excavators) has been done at the Hallmark Shipping/Receiving Dock, in order to prevent damage to new (asphalt) surfaces.

BOATYARD RESURFACING

Engineer's Estimate - 2/17/19

	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12
Month																								
Year	20												21											
1 Design & Project Engineering																								
2 Permitting																								
3 Erosion Control																								
4 Mobilization																								
5 Project Layout/Mtls. Testing																								
6 Site Preparation/Demolition																								
7 Excavation & Grading																								
8 Geotextile Fabric																								
9 Aggregate Sub-Base																								
10 Cleanouts & Catch Basins																								
12 Utility Boxes																								
13 Waterline Installation																								
14 3" Asphalt Overlay (215,000 sf) (150 lbs/cf)																								
15 Conveyance Pipe																								
16 Trench Drain																								
17 CIP Curb																								
18 Curb & Gutter																								
19 Concrete Sidewalk																								
20 Electric Conduit & Wiring																								
21 Lighting w Foundation																								
22 Landscaping & Plantings																								
23 Striping																								
24 Final Inspection																								

As is the case for the two previous proposed surfacing projects, this six-month period is best for completing this final proposed Phase III paving project, for at least 3 reasons: 1. The dry season begins in April at this location, providing amenable conditions for asphalt & concrete work; 2. This six-month time period is outside the in-water work period (Oct. - end of February), and so the surfacing work need not conflict with proposed in-water (dock repair/replacement) and 3. All resurfacing work should be done after that requiring heavy equipment (cranes, excavators) has been done at the Travel Lift Shipping/Receiving Dock, in order to prevent damage to

Port of Brookings Harbor: Fixed Fuel Dock-Sheet Pile Wall & Fuel Line Repair

Engineer's Estimate (Preliminary)
2/11/2019

Item No.	Item	Unit	Quantity	Unit Price	Total Price	Remarks
1	Final Project Design	LS	1	\$18,000	\$18,000	
2	Permitting	LS	1	\$15,000	\$15,000	Shared with Ice House, Pac-Choice, Old BC Fisheries Docks
3	Contractor Procurement	LS	1	\$3,000	\$3,000	Shared with Ice House, Pac-Choice, Old BC Fisheries Docks
4	Mobilization	LS	1	\$36,000	\$36,000	Shared with Ice House, Pac-Choice, Old BC Fisheries Docks
5	Erosion Control	LS	1	\$4,000	\$4,000	
6	Pollution Control Plan	LS	1	\$500	\$500	
7	Removal of Structures and Obstructions	LS	1	\$66,346	\$66,346	Anything man-made not removable as General Excavation, plus sloughed out fill and other soil outside limits of Gen. Exc.
8	Relocate Existing Outbuildings	LS	1	\$11,538	\$11,538	
9	General Excavation	Cy	700	\$5	\$3,500	Excavation to bottom of working pad
10	Stone Embankment	Cy	721	\$50	\$36,058	Clean 1 to 4 inch backfill below water
11	Cement Treated Soil	Cy	1125	\$7	\$7,875	Deadman CTS & upper 2-foot section only
12	Portland Cement	Ton	93	\$150	\$14,019	5% of CTS
13	Nonwoven Filter Geotextile	Sy	346	\$1	\$346	
14	Shoring	Sy	35	\$400	\$13,846	
15	Structure Excavation	Cy	35	\$15	\$519	Additional excavation for deadman below Gen. Exc. Backfill behind deadman and below CTS between sheet pile wall
16	Selected General Backfill	Cy	773	\$8	\$6,185	and deadman CTS, using on-site soils. Steel cost & \$25,000 shipping plus 15% mark-up & installation @ \$511,592 \$2700/pile
17	Furnish and Drive Steel Sheet Piling	Fl. ²	7308	\$70	\$511,592	
18	Furnish and Install Steel Tieback Rods	Fl	1826	\$32	\$58,431	Includes couplers, sleeves, grout, plates, etc.
19	Reinforcement	Lbs.	4269	\$1	\$4,696	
20	Coated Reinforcement	Lbs.	2596	\$1	\$3,245	
21	General Structural Concrete, Class 3300	Cy	118	\$500	\$59,135	Includes waler, water bolts, brackets, scaffolding, welding, plates, includes water, water bolts, brackets, scaffolding, etc..
22	Steel Channel Walers	Lbs.	9040	\$7	\$63,280	
23	Steel Ladders	Lbs.	404	\$10	\$4,038	All stainless steel.
24	Wharf Fenders	Fl.	297	\$20	\$5,942	
25	Aggregate Base	Cy	288	\$45	\$12,981	12" layer below CTS and sand fill.
26	Level 3, 1/2 Inch Dense MHMAC Mixture	Ton	72	\$150	\$10,817	
27	Remove and Reinstall Illumination	LS	1	\$3,462	\$3,462	
28	Furnish and Install Docks/Hoist	LS	1	\$15,000	\$15,000	
29	Backfill Former pad & walkway areas	Cy	270	\$5	\$1,350	
30	Fuel Line Update & Replacement	LF	250	\$128	\$32,000	Includes two sumps, installation
31	Demolish Old Fuel Dock	LS	1	\$7,000	\$7,000	Includes disposal
Subtotal of Biddable Items:						\$1,025,185
Contingencies @ 10%:						\$102,500
Construction Engineering @ 15%:						\$153,800
Construction Total:						\$1,281,485

Port of Brookings : Ice House-Sheet Pile Wall Repair

Engineer's Estimate (Preliminary)
2/10/2019

Item No.	Item	Unit	Quantity	Unit Price	Total Price	Remarks
1	Final Project Design	LS	1	\$18,000	\$1,000	
2	Permitting	LS	1	\$15,000	\$15,000	Shared with Fuel, Pac-Choice, Old BC Fisheries Docks
3	Contractor Procurement	LS	1	\$3,000	\$3,000	Shared with Fuel, Pac-Choice, Old BC Fisheries Docks
1	Mobilization	LS	1	\$36,000	\$36,000	Shared with Other Subprojects in Phase I
2	Erosion Control	LS	1	\$5,000	\$5,000	
3	Pollution Control Plan	LS	1	\$500	\$500	
4	Removal of Structures and Obstructions	LS	1	\$42,000	\$42,000	Anything man-made not removable as General Excavation
6	General Excavation	Cy	600	\$5	\$3,000	Excavation to bottom of working pad
10	Nonwoven Filter Geotextile	Sy	300	\$1	\$300	
11	Shoring	Sy	60	\$400	\$24,000	
13	Selected General Backfill	Cy	300	\$8	\$2,400	
21	Wharf Fenders	Fl.	350	\$20	\$7,000	Fenders already owned by Port
22	Aggregate Base	Cy	250	\$45	\$11,250	
Subtotal of Biddable Items:					\$150,450	
Contingencies @ 10%:					\$15,000	
Construction Engineering @ 15%:					\$5,000	
Construction Total:					\$170,450	

Port of Brookings Harbor: Pac-Choice Dock-Sheet Pile Wall Repair

Engineer's Estimate (Preliminary)
2/10/2019

No.	Item	Unit	Quantity	Unit Price	Total Price	Remarks
1	Final Project Design	LS	1	\$18,000	\$18,000	
2	Permitting	LS	1	\$15,000	\$15,000	Shared with Ice House, Fuel Dock, Old BC Fisheries Dock
3	Contractor Procurement	LS	1	\$3,000	\$3,000	Shared with Ice House, Fuel Dock, Old BC Fisheries Dock
4	Mobilization	LS	1	\$36,000	\$36,000	Shared w Other Subprojects in Phase I
5	Erosion Control	LS	1	\$4,500	\$4,500	
6	Pollution Control Plan	LS	1	\$500	\$500	
7	Removal of Structures and Obstructions	LS	1	\$77,404	\$77,404	Anyting man-made not removable as general excavation, plus sloughed out fill and other soil outside limits of Gen. Exc.
8	Relocate Existing Outbuildings	LS	1	\$13,462	\$13,462	
9	General Excavation	Cy	2558	\$5	\$12,788	Excavation to bottom of working pad
10	Stone Embankment	Cy	841	\$50	\$42,067	Clean 1 to 4 inch backfill below water
11	Cement Treated Soil	Cy	1313	\$7	\$9,188	Deadman CTS & upper 2-foot section only
12	Portland Cement	Ton	109	\$150	\$16,356	5% of CTS
13	Nonwoven Filter Geotextile	Sy	404	\$1	\$404	
14	Shoring	Sy	40	\$400	\$16,154	
15	Structure Excavation	Cy	40	\$15	\$606	Additional excavation for deadman below Gen. Exc.
16	Selected General Backfill	Cy	902	\$8	\$7,215	Backfill behind deadmen and below CTS between sheet pile wall and deadman CTS, using on-site soils.
17	Furnish and Drive Steel Sheet Piling	Fl. ²	8527	\$70	\$596,858	Steel cost & \$28,000 shipping plus 15% mark-up & installation @ \$2700/pile
18	Furnish and Install Steel Tieback Rods	Fl	2130	\$32	\$68,169	Includes couplers, sleeves, grout, plates, etc.
19	Reinforcement	Lbs.	4981	\$1	\$5,479	
20	Coated Reinforcement	Lbs.	3029	\$1	\$3,786	
21	General Structural Concrete, Class 3300	Cy	138	\$500	\$68,990	
22	Steel Channel Walers	Lbs.	10547	\$7	\$68,556	Includes waler, water bolts, brackets, scaffolding, welding, plates, installation, etc..
23	Steel Ladders	Lbs.	471	\$10	\$4,712	All stainless steel.
24	Wharf Fenders	Fl.	347	\$20	\$6,933	
25	Aggregate Base	Cy	337	\$45	\$15,144	12" layer below CTS and sand fill.
26	Level 3, 1/2 Inch Dense MHMAC Mixture	Ton	84	\$150	\$12,620	
27	Remove and Reinstall Illumination	LS	1	\$4,038	\$4,038	
28	Furnish and Install Docksides Hoist	LS	1	\$10,096	\$10,096	
						Subtotal of Biddable Items: \$1,138,025
						Contingencies @ 10%: \$113,800
						Construction Engineering @ 15%: \$170,700
						Construction Total: \$1,422,525

Port of Brookings : OLD BC Fisheries Dock-Sheet Pile Wall Repair

Engineer's Estimate (Preliminary)
2/20/2019

No.	Item	Unit	Quantity	Unit Price	Total Price	Remarks
1	Final Project Design	LS	1	\$18,000	\$18,000	
2	Permitting	LS	1	\$15,000	\$15,000	Shared with Ice House, Pac-Choice, Fuel Docks
3	Contractor Procurement	LS	1	\$3,000	\$3,000	Shared with Ice House, Pac-Choice, Fuel Docks
4	Mobilization	LS	1	\$36,000	\$36,000	0
5	Erosion Control	LS	1	\$5,000	\$5,000	
6	Pollution Control Plan	LS	1	\$500	\$500	
7	Removal of Structures and Obstructions	LS	1	\$79,615	\$79,615	Anything man-made not removable as General Excavation, plus sloughed out fill and other soil outside limits of Gen. Exc.
8	Relocate Existing Outbuildings	LS	1	\$13,846	\$13,846	
9	General Excavation	Cy	2631	\$5	\$13,154	Excavation to bottom of working pad
10	Stone Embankment	Cy	865	\$50	\$43,269	Clean 1 to 4 inch backfill below water
11	Cement Treated Soil	Cy	1350	\$7	\$9,450	Deadman CTS & upper 2-foot section only
12	Portland Cement	Ton	112	\$150	\$16,823	5% of CTS
13	Nonwoven Filter Geotextile	Sy	415	\$1	\$415	
14	Shoring	Sy	42	\$400	\$16,615	
15	Structure Excavation	Cy	42	\$15	\$623	Additional excavation for deadman below Gen. Exc.
16	Selected General Backfill	Cy	928	\$8	\$7,422	Backfill behind deadman and below CTS between sheet pile wall and deadman CTS, using on-site soils.
17	Furnish and Drive Steel Sheet Piling	Ft. ²	8770	\$61	\$538,049	Steel cost & \$30,000 shipping plus 15% mark-up & installation @ \$2700/pile
18	Furnish and Install Steel Tieback Rods	Ft	2191	\$32	\$70,117	Includes couplers, sleeves, grout, plates, etc.
19	Reinforcement	Lbs.	5123	\$1	\$5,635	
20	Coated Reinforcement	Lbs.	3115	\$1	\$3,894	
21	General Structural Concrete, Class 3300	Cy	142	\$500	\$70,962	
22	Steel Channel Walkers	Lbs.	10848	\$7	\$70,515	Includes waler, water bolts, brackets, scaffolding, welding, plates, installation, etc..
23	Steel Ladders	Lbs.	485	\$10	\$4,846	All stainless steel.
24	Wharf Fenders	Ft.	357	\$20	\$7,131	
25	Aggregate Base	Cy	346	\$45	\$15,577	12" layer below CTS and sand fill.
26	Level 3, 1/2 Inch Dense MHMAC Mixture	Ton	87	\$150	\$12,981	
27	Remove and Reinstall Illumination	LS	1	\$4,154	\$4,154	
28	Furnish and Install Dockside Hoist	LS	1	\$15,000	\$15,000	
<p align="right">Subtotal of Biddable Items: \$1,097,594</p> <p align="right">Contingencies @ 10%: \$109,800</p> <p align="right">Construction Engineering @ 15%: \$164,600</p> <p align="right">Construction Total: \$1,371,994</p>						

7

Phase I Access & Material Handling Surfaces

Engineer's Estimate: 2/23/19

Item	Qty	Unit	Unit Cost	TOTALS
Design & Project Engineering	1	LS	\$18,500	\$18,500
Permitting	1	LS	\$2,000	\$2,000
Mobilization	1	LS	\$90,000	\$90,000
Project Layout/Mtls. Testing	1	LS	\$10,500	\$10,500
Site Preparation/Demolition	1	LS	\$60,000	\$60,000
Excavation & Grading (R&R)	12000	cy	\$16	\$192,000
Geotextile Fabric	215000	sf	\$0	\$53,750
SW Management (sediment fencing & erosion control)	500	LF	\$5	\$2,500
Aggregate Sub-Base	5200	CY	\$35	\$182,000
12" Cleanouts	4	EA	\$1,000	\$4,000
Catch Basins	10	EA	\$1,500	\$15,000
Utility Boxes &/or Relocations	2	LS	\$4,000	\$8,000
3" Asphalt Overlay (215,000 sf) (150 lbs/cf) w 25% overage.	5040	TON	\$110	\$554,400
12" pipe	768	LF	\$50	\$38,400
Trench Drain	280	LF	\$100	\$28,000
CIP Curb	5600	LF	\$15	\$84,000
Curb & Gutter	606	LF	\$25	\$15,150
Concrete Sidewalk	7000	SF	\$7	\$49,000
Electric Conduit & Wiring	720	LF	\$25	\$18,000
Lighting w Foundation	4	EA	\$4,000	\$16,000
Landscaping & Plantings	1	LS	\$10,000	\$10,000
Striping	800	LF	\$1	\$800
Waterline Installation/Replacement	10	LS	\$5,000	\$50,000
TOTAL				\$1,502,000

PHASE IIIa and IIIb - COMBINED TRANSIENT AND WORK DOCK

2/23/19 Engineer's Estimate

No.	Task Name	Unit	Quantity	Cost/Unit	Total Costs
1	Engineering Design	LS	1	\$4,500	\$4,500
2	Permitting	LS	1	\$14,000	\$14,000
3	Contractor Procurement	LS	1	\$3,500	\$3,500
4	Project Engineering/MGMT.	LS	1	\$4,400	\$4,400
5	Fencing and erosion control, Pollution Control Plan	LS	1	\$4,000	\$4,000
6	Removal of corroded, fallen or creosote-treated piles (12"-18" diameter, Est. 30' - 45' long)	ea	45	\$1,000	\$45,000
7	Placement of 60 foot long, 12" and 18" dia., 1/2" - 5/8" t steel piles, via vibratory hammer	ea	45	\$4,800	\$216,000
8	Corrosion-resistant pile coating	LF	11	\$2,700	\$29,700
9	Hoops, caps, washer plate, fasteners, including shipping.	ea	45	\$2,000	\$90,000
10	Dock Waler Repair	ea	32	\$1,250	\$40,000
10	Equipment renting, mobilizing, putting in place, demobilizing	LS	1	\$140,000	\$140,000
	TOTALS				\$591,100

Note: The unit prices include all labor, materials, overhead, profit, insurance, etc., to cover the finished work. This project is funded, at least in part, by federal & Oregon-state grants, and so bids

TRAVEL LIFT DOCK REPLACEMENT

Engineer's Estimate: 2/23/19

Item	Qty	Unit	Unit Cost	TOTALS
Design & Project Engineering	1	LS	\$90,000	\$90,000
Permitting	1	LS	\$19,000	\$19,000
SW Management (sediment fencing & erosion control)				
Mobilization	1	LS	\$48,000	\$48,000
Project Layout/Mtls. Testing	1	LS	\$10,500	\$10,500
Site Preparation/Demolition	1	LS	\$75,000	\$75,000
Pile & Structure Removal	110	ea	\$1,000	\$110,000
Steel Pile Supply & Driving	60	ea	\$5,800	\$348,000
Steel Beam & Bracing	60	ea	\$2,900	\$174,000
Platform & Tracks Construction	190	LF	\$600	\$114,000
Load Testing	1	LS	\$6,500	\$6,500
Demobilization	1	LS	\$48,000	\$48,000
Final Inspection	1	LS	\$7,500	\$7,500
TOTAL				\$1,050,500

Port of Brookings Harbor - Hailmark Dock Sheet Pile Wall Repair

Engineer's Estimate (Preliminary)
2/22/2019

Item No.	Item	Unit	Quantity	Unit Price	Total Price	Remarks
1	Final Project Design	LS	1	\$18,000	\$18,000	
2	Permitting	LS	1	\$8,500	\$8,500	Shared with the Other Subprojects
3	Contractor Procurement	LS	1	\$3,000	\$3,000	Shared with the Other Subprojects
4	Mobilization	LS	1	\$180,000	\$180,000	
5	Erosion Control	LS	1	\$5,000	\$5,000	
6	Pollution Control Plan	LS	1	\$500	\$500	
7	Removal of Structures and Obstructions	LS	1	\$88,462	\$88,462	Anything man-made not removable as General Excavation, plus sloughed out fill and other soil outside limits of Gen. Exc.
8	Relocate Existing Outbuildings	LS	1	\$15,385	\$15,385	
9	General Excavation	Cy	2923	\$5	\$14,615	Excavation to bottom of working pad
10	Stone Embankment	Cy	962	\$50	\$48,077	Clean 1 to 4 inch backfill below water
11	Cement Treated Soil	Cy	1500	\$7	\$10,500	Deadman CTS & upper 2-foot section only
12	Portland Cement	Ton	125	\$150	\$18,692	5% of CTS
13	Nonwoven Filter Geotextile	Sy	462	\$1	\$462	
14	Shoring	Sy	46	\$400	\$18,462	
15	Structure Excavation	Cy	46	\$15	\$692	Additional excavation for deadman below Gen. Exc.
16	Selected General Backfill	Cy	1031	\$8	\$8,246	Backfill behind deadmen and below CTS between sheet pile wall and deadman CTS, using on-site soils.
17	Furnish and Drive Steel Sheet Piling	Sy	9745	\$61	\$597,832	Steel cost @ \$2700/pile
18	Furnish and Install Steel Tieback Rods	Fl	2435	\$32	\$77,908	Includes couplers, sleeves, grout, plates, etc.
19	Reinforcement	Lbs.	5692	\$1	\$6,262	
20	Coated Reinforcement	Lbs.	3462	\$1	\$4,327	
21	General Structural Concrete, Class 3300	Cy	158	\$500	\$78,846	Includes waler, water bolts, brackets, scaffolding, welding, plates, installation, etc..
22	Steel Channel Walers	Lbs.	12054	\$7	\$78,350	
23	Steel Ladders	Lbs.	538	\$10	\$5,385	All stainless steel.
24	Wharf Fenders	Fl.	396	\$20	\$7,923	
25	Aggregate Base	Cy	385	\$45	\$17,308	12" layer below CTS and sand fill.
26	Level 3, 1/2 Inch Dense MHMAC Mixture	Ton	96	\$150	\$14,423	
27	Remove and Reinstall Illumination	LS	1	\$4,615	\$4,615	
28	Furnish and Install Docksides Hoist	LS	1	\$11,538	\$11,538	
Subtotal of Biddable Items:					\$1,343,309	
Contingencies @ 10%:					\$134,300	
Construction Engineering @ 15%:					\$201,500	
Construction Total:					\$1,679,109	

**Phase IIIb Hallmark Gear
Storage/Access Surfaces**

Engineer's Estimate: 2/21/19

Item	Qty	Unit	Unit Cost	TOTALS
Design & Project Engineering	1	LS	\$6,500	\$6,500
Permitting (Shared)	1	LS	\$2,000	\$2,000
Mobilization (Shared)	1	LS	\$47,250	\$47,250
Project Layout/Mtls. Testing	1	LS	\$7,000	\$7,000
Site Preparation/Demolition (109 k sf)	1	LS	\$41,972	\$41,972
Excavation & Grading (R&R)	8394	cy	\$16	\$134,312
Geotextile Fabric	243440	sf	\$0	\$60,860
SW Management (sediment fencing & erosion control)	700	LF	\$5	\$3,498
Aggregate Sub-Base	7275	CY	\$35	\$254,633
12" Cleanouts	3	EA	\$1,000	\$2,798
Catch Basins	14	EA	\$1,500	\$20,986
Utility Boxes &/or Relocations	3	LS	\$4,000	\$11,193
3" Asphalt Overlay (90,000 sf) (150 lbs/cf) w 25% overage.	5901	TON	\$110	\$649,146
12" pipe	1074	LF	\$50	\$53,725
Trench Drain	392	LF	\$100	\$39,174
CIP Curb	7835	LF	\$15	\$117,523
Curb & Gutter	848	LF	\$25	\$21,196
Concrete Sidewalk	9794	SF	\$7	\$68,555
Electric Conduit & Wiring	1007	LF	\$25	\$25,183
Lighting w Foundation	6	EA	\$4,000	\$22,385
Landscaping & Plantings	1	LS	\$27,982	\$27,982
Striping	1119	LF	\$1	\$1,119
Waterline Installation/Replacement	1	LS	\$13,991	\$13,991
TOTAL				\$1,632,982

**Phase III c Boatyard
Storage/Access Surfaces**

Engineer's Estimate: 2/21/19

Item	Qty	Unit	Unit Cost	TOTALS
Design & Project Engineering	1	LS	\$6,500	\$6,500
Permitting (Shared)	1	LS	\$2,000	\$2,000
Mobilization (Shared)	1	LS	\$47,250	\$47,250
Project Layout/Mtls. Testing	1	LS	\$7,000	\$7,000
Site Preparation/Demolition	1	LS	\$18,853	\$18,853
Excavation & Grading (R&R)	3771	cy	\$16	\$60,330
Geotextile Fabric	109349	sf	\$0	\$27,337
SW Management (sediment fencing & erosion control)	314	LF	\$5	\$1,571
Aggregate Sub-Base	3268	CY	\$35	\$114,376
12" Cleanouts	1	EA	\$1,000	\$1,257
Catch Basins	6	EA	\$1,500	\$9,427
Utility Boxes &/or Relocations	1	LS	\$4,000	\$5,028
3" Asphalt Overlay (90,000 sf) (150 lbs/cf) w 25% overage.	2651	TON	\$110	\$291,584
12" pipe	483	LF	\$50	\$24,132
Trench Drain	176	LF	\$100	\$17,596
CIP Curb	3519	LF	\$15	\$52,789
Curb & Gutter	381	LF	\$25	\$9,521
Concrete Sidewalk	4399	SF	\$7	\$30,794
Electric Conduit & Wiring	452	LF	\$25	\$11,312
Lighting w Foundation	3	EA	\$4,000	\$10,055
Landscaping & Plantings	1	LS	\$12,569	\$12,569
Striping	503	LF	\$1	\$503
Waterline Installation/Replacement	1	LS	\$6,284	\$6,284
TOTAL				\$768,067

EXHIBIT A

OLD BC DOCK - Support Structure



EXHIBIT A



EXHIBIT A

PAC-CHOICE DOCK- Support Structure




EXHIBIT A

HALLMARK DOCK- Support Structure




EXHIBIT A

ICE HOUSE DOCK- Support Structure



EXHIBIT A

TRAVEL LIFT DOCK- Support Structure



EXHIBIT A

FUEL RECEIVING DOCK- Support Structure



EXHIBIT A

TRANSIENT DOCK- Support Structure



WORK DOCK- Support Structure




EXHIBIT A

BC Fisheries - Support Structure



EXHIBIT B

OLD BC DOCK – Surfaces



EXHIBIT B

PAC-CHOICE DOCK- Surfaces





EXHIBIT B



HALLMARK DOCK- Surfaces




EXHIBIT B





EXHIBIT C

Dock Access, Parking & Material Handling






EXHIBIT C



EXHIBIT C




Looking Westward from Lower Harbor Road




Looking Northwestward from Lower Harbor Road

EXHIBIT C



Looking Southwestward from Lower Harbor Road



Looking Westward from Lower Harbor Road